

# Welcome



## Restoration Advisory Board (RAB) Meeting

Robins Air Force Base (AFB)

March 12, 2026



# **Welcome and Program Introduction**

**Mr. Heyward Singleton  
RAB Installation Co-chair**



# Acronyms and Abbreviations

---

- **COC - Contaminant of Concern**
- **DPT - Direct Push Technology**
- **FFA - Federal Facilities Agreement**
- **FYR - Five-Year Review**
- **GA EPD - Georgia Environmental Protection Division**
- **LF004 - Landfill No. 4**
- **LUC - Land Use Control**
- **MNA - Monitored Natural Attenuation**
- **NPL - National Priorities List**
- **O&M - Operations and Maintenance**
- **OU - Operable Unit**
- **PFAS - Per- and Polyfluoroalkyl Substances**



# Acronyms and Abbreviations

---

- **RA-O - Remedial Action - Operation**
- **RAO - Remedial Action Objective**
- **TCE - Trichloroethene**
- **USACE - United States Army Corps of Engineers**
- **USEPA - United States Environmental Protection Agency**
- **VOC - Volatile Organic Compound**



# Restoration Advisory Board

---



## Five-Year Review (FYR) for National Priorities List (NPL) Site

**Fred Otto**  
**Restoration Program Manager**  
**AFCEC/CZRE**

**March 12, 2026**



# Sixth FYR for NPL Site

## ■ Purpose of FYR

- Comprehensive evaluation of remedial progress
- Determine if the remedy selected for the site remains protective of human health and the environment





# Sixth FYR for NPL Site



- **Operable Unit 1 (OU1)**
  - **Landfill No. 4 (LF004)**
    - 45-acre landfill
    - Operated 1965 to 1978
    - General refuse and industrial waste
  - **Waste Pit 14 (WP014)**
    - 1.5-acre Sludge Lagoon
    - Operated 1962 to 1978
    - Industrial waste treatment plant sludge
- **Operable Unit 3 (OU3)**
  - **Groundwater impacted by releases from OU1**
    - Volatile organic compounds (VOCs) and metals



# Sixth FYR for NPL Site

## ■ OU1 (LF004 and WP014) Remedies

- **WP014 treatment**

- In-situ volatilization, excavation, and solidification (1996)

- **LF004 engineering and institutional controls**

- Cover system with geocomposite liner (1998)
- Passive landfill gas venting system (1998)
- Stormwater management controls (1998)
- Land Use Controls (LUCs)



LF004 Passive Gas Vent



LF004 LUC (Fence and Locked Gate)



# Sixth FYR for NPL Site

- **OU3 (Groundwater) remedies**
  - Groundwater recovery and treatment system installed (1997)
  - Groundwater recovery ceased (2007)
  - Monitored Natural Attenuation (MNA) study initiated (2007)
  - Final approval to transition to MNA (2010)



Groundwater Treatment Plant



# Sixth FYR for NPL Site

---

- **Comprehensive evaluation of remedy to determine if it remains protective of human health and the environment**
  - LUCs
  - Groundwater MNA



# Sixth FYR for NPL Site

---

- **Interim Record of Decision (ROD) – September 1995**
- **First FYR – March 2001**
- **Final ROD – September 2004**
- **Second FYR – June 2006**
- **Third FYR – September 2011**
- **Fourth FYR – June 2016**
- **Fifth FYR – August 2021**
- **Sixth FYR – Due 29 June 2026**
  - **Behind schedule due to funding delay**



# Sixth FYR for NPL Site

---

- **FYR process typically 18 months**
- **FYR funding programmed for beginning of 2025, but not received until late August 2025**
- **FYR being conducted by United States Army Corps of Engineers (USACE) in-house to expedite schedule**



# Restoration Advisory Board

---



## LF004 Update on Progress

**Ms. Elizabeth Rhine  
Bhate Environmental**

**March 12, 2026**



# Overview

---

- **Background**
- **Cover system**
- **LUCs**
- **Inspections and Maintenance**
- **Groundwater**
- **Path Forward**



# Background

- 45-acre inactive landfill
- Used between 1965 and 1978 for disposal of general refuse and industrial wastes
- Former Sludge Lagoon (WP014) is located within LF004 boundary





# Background

---

## LF004 is divided into three OUs

### 1) OU1 - Landfill and WP014

- Geocomposite cover system and passive landfill gas ventilation system installed over entire surface of LF004, including WP014, as part of cover renovation activities in September 1998
- Operations and maintenance (O&M) of LF004 began in October 1998

### 2) OU2 - Wetlands and Surface Water

- Granted No Further Action status on 29 September 2006

### 3) OU3 - Groundwater

- Groundwater recovery system operated from 1997 to 2007 when it was replaced with MNA



# Background

---

- **Placed on NPL in 1987**
- **Administered under a Federal Facilities Agreement (FFA) signed 14 June 1989**
- **Final ROD submitted to United States Environmental Protection Agency (USEPA) in 2000 and approved on 30 September 2004**



# Background

---

- **Remedial action objectives (RAOs) of containment and exposure control addressed with:**
  - Source area treatment (implemented in 1996)
  - Landfill cover system (1998)
  - Passive venting of landfill gas (1998)
  - Surface water (runoff) controls (1998)
  - LUCs and quarterly inspections (ongoing)
  - Groundwater remediation (1997)
- **Optimized Remediation Contract Performance Objective: Remedial Action - Operation (RA-O)**



# Background

---


- **OU1 - Landfill and Sludge Lagoon Waste Pit 14 (WP014)**
  - **1.5-acre unlined lagoon used from 1962 to 1978 to dispose sludge from industrial wastewater treatment plant and other miscellaneous industrial wastes**
  - **Phenols, heavy metals, cyanide, solvents, cleaners, paint removers, hydraulic fluids, and oils**
  - **WP014 was closed in 1978 and capped with a clayey sand cover approximately 5 feet thick**
  - **Waste was treated in 1996 by in situ volatilization followed by excavation and solidification; solidified sludge was placed on top of LF004 and covered**



# Cover System


## TYPICAL PASSIVE GAS VENT SCHEMATIC

(SOURCE: LANDFILL COVER RENOVATION DESIGN, LOCKHEED MARTIN, 1997)



## TYPICAL LANDFILL NO. 4 AND SLUDGE LAGOON CAPPING SYSTEM


(SOURCE: FINAL RECORD OF DECISION (ROD), FOR THE NATIONAL PRIORITIES LIST (NPL) SITE, OPERABLE UNITS (OUs) 1 AND 3, EARTH TECH, SEPTEMBER 2004)



- NOTES:
- |                              |  |
|------------------------------|--|
| 1. FIGURES ARE NOT TO SCALE. | 7. NO. = NUMBER                        |
| 2. ° = DEGREE                | 8. NPT = NATIONAL PIPE THREAD          |
| 3. ' = FEET (FOOT)           | 9. OZ = OUNCE                          |
| 4. IN = INCH(ES)             | 10. PVC = POLYVINYL CHLORIDE           |
| 5. * = INCH(ES)              | 11. SST = STAINLESS STEEL TYPE         |
| 6. MIL = 0.001 INCH          | 12. SWMU = SOLID WASTE MANAGEMENT UNIT |



# Cover System



**Legend**

- LF4GV22 8: Landfill Gas Vent Identification
- Average Annual Landfill Gas Reading (percent methane by volume)

**Site Features**

- Gas Vent Location
- Gas Vent Piping
- Former WP-14 Sludge Lagoon
- LF004 Boundary
- LF004 Areas Boundary
- Stormwater Drain
- Approximate Location of Quaternary Alluvium Contact
- Water Body
- Building Number



**Notes:**  
 1. Aerial Photograph Date: 3 March 2022  
 2. Methane gas readings were measured quarterly from January to December 2024, then averaged to obtain the Average Annual Landfill Gas Reading.

<b>PROJECT NAME:</b> 2024 ANNUAL OPERATIONS, MAINTENANCE, AND INSPECTION REPORT FOR LANDFILL NUMBER 4 (LF004) OPTIMIZED REMEDIATION CONTRACT (ORC) ROBINS AFB, GEORGIA	
<b>FIGURE DESCRIPTION:</b> LANDFILL GAS VENTS AND AVERAGE ANNUAL METHANE CONCENTRATIONS	<b>FIGURE NO.:</b> 2
<b>CONTRACT NO./TASK ORDER NO.:</b> W512EP16C0009W5 (24NDZF102)	<b>PREPARED BY:</b> MM <b>CHECKED BY:</b> JH <b>DATE:</b> 03/04/2025



# Cover System





# Land Use Controls


Land Use Control	Maintenance and Quarterly Inspection Requirements
No ground-disturbing activities	Landfill surface visually inspected and maintenance performed as necessary to meet land use control objectives for OU3
Restrict access by maintaining gates at each entry point	Fencing inspected and maintenance performed when required
Maintain signage at each entrance and at other locations	Signage inspected and maintenance performed when required
Prohibit use of water from supply wells	Restricted access to site, and fencing around site with signage that states restricted access

**Perimeter fences and gates**





# Land Use Control Boundary





# Inspections

---

- Quarterly measurement of landfill gas concentrations at passive ventilation units
- Quarterly inspection of landfill cover system to assess its integrity and completion of as-needed repairs
- Quarterly inspection and maintenance of LUCs
- Routine maintenance of cover system, including mowing, removing shrubs and trees, restoring areas of surface erosion and hog damage, fertilizing, and re-vegetating or grassing
- Preparation and submittal of annual Operations, Maintenance, and Inspection Report documenting related activities
- FYRs



# Inspections - Methane Readings



Vent Wells



Screen Maintenance



Landfill Gas Meter



# Maintenance - Water Conveyance

## ■ Stormwater conveyance system repair



Removal of vegetation, grading, placement of concrete surface, and final restoration.

Completed March 2013.





# Maintenance – Water Conveyance

## ■ Stormwater conveyance system repair



Removal of vegetation, grading, placement of concrete surface, and final restoration.

Completed March 2013.





# Maintenance – Water Conveyance

- Clearing and grubbing; herbicide application



2025 Pre- and  
Post-Clearing



# Maintenance - Water Conveyance



Erosion at Inlet



Erosion Repair at Inlet



Clearing and  
Grubbing at  
Outlet



# Maintenance – Fence Repair





# Maintenance - Tree Harvesting

- Performed in 2022 at end of runway
- Harvesting equipment damaged wells





# Maintenance - Wildlife Control



Wild Hog Rooting



Repair of Vegetative Cap




# Groundwater

---

- **Groundwater recovery system of six recovery wells and four leachate pump stations were installed at OU3 in 1997**
- **Groundwater and leachate collected by system was treated at groundwater treatment plant until February 2007 when system was shut down and replaced with MNA per USEPA and Georgia Environmental Protection Division (GA EPD) approval**



# Groundwater






# Groundwater

## MNA remedy components

- VOC and geochemical parameter analyses
- Generation and evaluation of time-series graphs
- Temporal plume comparisons
- Statistical analysis of data trends (Mann-Kendall)
  - With exception of benzene (LF4-6 and LF4-52) and chlorobenzene (LF4-52 only), contaminants of concern (COCs) are stable or decreasing in all other wells







# Groundwater

---

## ■ Overall observations

- VOC concentrations have reduced over time due to groundwater recovery and MNA
- Reducing conditions in portions of aquifer are sustaining biological degradation of chlorinated VOCs
- Plume footprint is stable to decreasing
- Plume footprint is well within LUC boundary



# Path Forward

---

- **Continue quarterly inspections**
- **Perform maintenance as needed (e.g., remove debris that accumulates around drain inlets, restore hog damage, restore erosion)**
- **Sample groundwater annually**
- **Continue to optimize monitoring well network**
- **FYR completion in 2026 (currently underway)**



# Restoration Advisory Board

---



## Results of FYR for NPL Site

Jennifer Richards  
USACE, Savannah District

March 12, 2026



# FYR Overview

---

- **Process**
- **Results**
- **Summary**



# FYR Process

---

- **Develop review team**
- **Notify regulators and community of initiation of FYR process**
- **Conduct site inspection**
- **Complete technical assessment and associated reporting**
- **Notify regulators and community of results**



# FYR Process

---

## ■ FYR Team

- Robins AFB
- US EPA
- GA EPD
- USACE



# FYR Process

---

- **Scoping meeting – 8 October 2025**
- **Site inspection**
  - **FYR site visit occurred 19 November 2025 – US EPA visit**
- **Technical assessment and reporting for FYR**
  - **Draft FYR submitted to Robins AFB – February 2026**
  - **Draft FYR submitted to regulators – April 2026**
  - **Regulatory approved FYR – To be determined**
  - **Signed FYR – To be determined**
- **Notification of results**
  - **September 2026 RAB**



# FYR Results

- **OU1 - LF004 and WP14**
  - **RAOs**
    - Containment
    - Exposure control
  - **RAOs are being met**
    - Cover system
    - Surface water control
    - Passive landfill gas collection
    - Site access control
    - Continued inspection and maintenance





# FYR Results

---

## ■ OU3 – Groundwater

- RAOs

- Containment and exposure controls
- Prevent potential groundwater contaminant impact to adjacent wetlands
- Restore groundwater to Maximum Contaminant Levels (MCLs)

- **First two are being met; continued significant progress toward groundwater restoration**



# FYR Results

---

- **Trichloroethene (TCE) concentrations continue to decrease under MNA**
- **Overall aerial extent of LF004 plumes continues to decrease**
- **Time to achieve RAOs with MNA continues to be reasonable**
- **Protectiveness statement**
  - **Remedy is protective of human health and the environment**
  - **Potential exposure pathways are controlled through landfill cover system and implementation of LUCs**



# FYR Summary

---

- Remedial actions at LF004 are protective of human health and the environment
- Report will be placed in Administrative Record, which is available to public
- Next FYR scheduled for June 2031

# Environmental Advisory Board

---



## Progress Update: Remedial Investigation of Per- and Polyfluoroalkyl Substances (PFAS)

Sam Santoso  
Oneida Environmental Services Group

March 12, 2026




# Remedial Investigation of PFAS Completed Work

- Borings Completed
  - $\approx$  633 (100%)
- Samples Collected
  - > 1,650 (soil and groundwater)
- Baseline Groundwater Sampling
  - $\approx$  80 existing monitoring wells
- Surface Water and Sediment Sampling
  - 15 locations



Solid green shaded = Direct Push Technology (DPT) boring complete






# Remedial Investigation of PFAS

## Ongoing Work

- **Monitoring Wells Completed**
  - $\approx 177$  (95%)
- **Samples Collected**
  - $\approx 350$  (soil)
- **Lysimeters Installed**
  - 18 (100%)
- **NPL site (WP014) attempted but not completed due to EPA review**



Solid orange shaded = Monitoring well installation complete

Orange hatch = Monitoring well installation not completed






# Remedial Investigation of PFAS

## Ongoing Work

- **Monitoring Wells Sampled**
  - $\approx 225/247$  (91%)
- **Lysimeters Sampled**
  - 13 (72%)
  - 5 did not hold vacuum
- **Groundwater Samples Collected**
  - $\approx 225$
- **Three more quarterly sampling events for lysimeters and one more bi-annual groundwater sampling of all wells (247)**



Solid blue shaded =  
Monitoring well  
sampling complete

Blue outline =  
Monitoring well  
sampling not  
planned at this time







# Remedial Investigation of PFAS

## Timeline

---

- **Contract Award - August 2022**
- **Planning Documents/Review - March 2023**
- **Field Preparations - May 2023**
- **Field Work/Data Collection - September 2023 to July 2027**
  - **Field work started late May 2025 for monitoring well installation and additional soil sampling**
  - **Field work is estimated to finish by February 2027**
- **Report Preparation - November 2026 through August 2027**



# **New Business and Program Closing**

**Mr. Singleton  
RAB Installation Co-chair**



# Next RAB Meeting

Thursday, September 10, 2026





**Please...**

**Complete meeting evaluation and  
feedback form and leave at your seat**

**Leave your name tag at sign-in table for next  
meeting**

**Thank you!**